


24	Time delay thermostat	ES2501/250W/10A/K45/TVV	1
23	Inner casing	SPCC	1
22	Internal stent dom	SPCC	1
21	Rubber feet	PP	4
20	Steel pipe	ø16*1.0mm	1
19	Pinching screw	φ8*35mm/PA	2
18	Plastic gasket	φ8mm Rubber	2
17	Outer casing	SPCC	1
16	Motor support	SPCC	1
15	Motor	TKS-24-42 24-34W/384V/30V	1
14	Fan	ø160mm	1
13	Fan fixing plate	φ4*28*1.0mm/SPCC	1
12	Control box	ABS V2 black	1
11	Handle cover	ABS V2 black	1
10	Thermostat knob	PA66 black	1
9	Switch knob	PA66 black	1
8	Rotary switch	250V/15A/70E	1
7	Temperature controller	250V AC 16A 85° C	1
6	Relay bracket	SPCC	1
5	Relay	JRC-7E-7E-2A 200-240V AC 3A	1
4	Internal stent up	SPCC	2
3	Re-set thermostat	250V 16A 45° C	1
2	Teblar electric heating element	220V-240V 50Hz 1650W	3
1	Ket cover	SPCC	2
Qty No.	Description	Material / Specifications	QTY

Project	Vega 50	Part No.	Parameter
---------	---------	----------	-----------

Designer	Standard	Units	m m
Check	Approval	Scale	

Krüger Technology S.L.		Model Name	Exploded diagram
		Drawing No.	